CHITALDRUG DIVISION.

Abstract Notification, dated 4th March 1903.

Repairing the Nagasamudra Tank Register No. 114 of Molakalmuru Taluk.

Attention is invited to tenders called for the above work in the *Mysore Gazette*, dated 12th March 1903.

The 11th March 1903.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 12 noon of 22nd March 1903, for additions and alterations to the Sub-Taluk Cutcherry at Hosdurga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1903.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for additions and alterations to the Sub-Taluk Cutcherry at Hosdurga," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates tendered should include royalty on stones to be paid to Government.

Additions and alterations to the Sub-Taluk Cutcherry at Hosdurga.

Item of work.	Unit.	Extension.	Lock-up	Barr Sepoys' huts.	Additions & alterations.	Total.
Earthwork ...	C.yd.	307	98	75	...	480
Burnt stone in mortar ...	C.ft.	9304	1263	1858	..	12425
Do arch work ...	Do	150	..	...	..	150
Burnt brick in chunam ...	Do	942	4325	493	..	5760
Cut stone work ...	Do	66	...	...	...	66
Burnt stone pillars with cuttings grooved	Each	32	...	...	...	32
Burnt stone slabs 6" thick, dressed ...	S.ft.	324	380	80	73	857
Do do ...	Do	169	..	...	...	169
Do dressing (nicely) ...	Do	70	...	...	...	70
Archwork brick in chunam ...	C.ft.	...	15	...	..	15
Burnt brick in mud ...	Do	9	..	1862	..	1862
Concrete filling ...	Do	...	1012	...	...	1012
Plastering with chunam ...	Sqr.	36·72	66·91	12·71	..	116·34
Do with mud ...	Do	...	..	33·58	..	33·58
Whitewashing ...	Do	36·72	66·91	46·29	80·00	229·92
Pointing with chunam ...	Do	66·00	...	2·22	...	68·22
Flooring with Mangalore square tiles over 3" concrete and cement pointing over (9" gravel).	Do	1·80	...	...	13·95	15·75
Flooring with slabs stones over 3" concrete and cement pointed.	Do	10·80	..	..	...	10·80
Filling with gravel (basement) ...	C.yds.	41	..	..	..	41
Coping with burnt brick in chunam ...	R.ft.	6	..	..	...	6
Terrace pucka 9" thick ...	Sqr.	14·93	..	...	...	14·93
Cornice work as per plan ...	R.ft.	294	..	..	..	294
Teakwood work wrought and put up ...	C.ft.	251·91	87·23	...	..	339·14
Teakwood planks 2" thick to record room	S.ft.	619	..	...	...	619
Wood oiling ...	Sqr.	15·74	2·68	8·00	22·46	48·88

Items of work.	Unit.	Extension.	Lockup.	Barr Sepoys' huts.	Additions & alterations.	Total.
Teakwood doors, double shutters with fitting, including chacolate painting ½ venetioned and ½ panelled.	Each	2	5	...	2	9
Do ½ battened, ½ barred doors with frames.	Do	...	2	..	....	2
Jungle work (honne) wrought and put up.	C,ft.	...	...	102	...	102
Do doors.	Each	..	..	8	..	8
Do ventilators	Do	..	...	8	...	8
Teakwood ventilators with iron bars and perforated webbing.	Do	...	11	..	.	11
Teakwood windows, double shutters battened outside, glass shutters inside and iron-barred ventilators at top, complete, including painting.	Do	10	..	..	1	11
Teakwood windows, double shutters, and iron bars etc., complete.	Do	...	2	...	...	2
Roofing with 1st class Mangalore tiles, teak reepers, etc., complete.	Sqr.	...	13·23	17·67	...	30·90
Ridge set in mortar and cement-pointed	R.ft.	..	36	57	...	93
Flooring with Cuddapah slabs over 3" concrete and cement-pointed.	Sqr.	..	5·31			5·31
Do with 6" concrete plastering etc. complete.	Do	..	...	7·68	...	7·68
Teakwood gates with iron work etc. complete.	Each	2	...	..	..	2
Chacolate painting	Sqr.	...	..	..	9·80	9·80
Jungle-wood eave-boards	R.ft.	..	..	150	..	150
Date stone	Each	..	1	1	..	2
Blocking up door-ways etc.	..	..	...	..	L. S.	...
Zinc gutters for draining water	...	L. S.	...	..	..	..
Ditching all round the building	...	..	L. S.	..	...	..
Clearing site and levelling	...	L. S.	L. S.	L. S.	..	..
Teakwood eave-boards	R.ft.	..	146	..	...	146
Ceiling with ½" teak planks including wood oiling.	Sqr.	..	5·70	...	..	5·70

Y. SRINIVASA RAO, *Executive Engineer.*

BANGALORE CITY MUNICIPALITY.

Notice, dated 16th March 1903.

The following business will be transacted at an Ordinary Meeting of the Municipal Commissioners for the City of Bangalore, to be held at their office premises now transferred to the building in the District Office road, where the Bangalore Taluk Office was hitherto being held, at 7-30 A.M., on Thursday the 26th March 1903:—

Deferred Proposition.

1. Plan and estimate amounting to Rs. 7,859 for the construction of a new slaughter-house.

Ordinary Propositions.

2. Cash Account Current, Demand, Collection and Balance Statement, Mortuary Return, Progress Report of Works, Memo of Visitors to the Srinivasa Mandiram Library, City Municipal English and Kanarese Schools Returns, Maternity Return, Langarkhana Return, Statement of Materials and Statement of Rewards for the Destruction of Dogs, and Return of Prosecutions, for February 1903.

3. Government Proceedings No. 13109-14—L. F. 11-02, dated the 26th February 1903, sanctioning the budget estimates of receipts and expenditure of the Bangalore City Municipality for 1902-03.

4. Correspondence ending with docket No. 43, dated the 20th February 1903, from the Honorary Secretary to the City Municipal Schools Committee, regarding the abolition of the post of Tamil teacher in the City Municipal English School together with a numerously signed petition from the inhabitants of Bangalore, complaining against the said abolition.

5. Petition of Khader Mohadeen Meccai, Hindustani teacher, Central College, applying for compensation for his land and building in the old timber yard to the north of the Mysore road, which was acquired in 1897 for the purpose of the proposed railway siding to the New Tharagupete.

6. Government Proceedings No. 13258—L. F. 38-02, dated the 3rd March 1903, declining, with certain observations, to sanction the loan of Rs. 10,000 for the construction of huts for the Mill labourers and other cooli population.

7. Estimate amounting to Rs. 350 for filling the fort karanji pond.

P. PALPU, for *President.*